

Meeting Attachments

council@shoalhaven.nsw.gov.au | shoalhaven.nsw.gov.au f @ - >

Special Shoalhaven Traffic Committee

Meeting Date: Thursday, 23 March, 2023

Location: Email Meeting

Attachments (Under Separate Cover)

Index

| 3. | Reports o | f the Convenor | |
|----|-----------|---|----|
| | TC23.17 | Proposed Temporary Event Traffic Control Measures - Blessing of the Fleet - Ulladulla CBD (PN 3750) | |
| | | Attachment 1 PN 3750 Plans | 2 |
| | TC23.18 | Proposed Temporary Event Traffic Control Measures - Berry Showground - Lazy Mountain Festival - Berry (PN 3751) | |
| | | Attachment 1 PN 3751 TMP | 35 |



Ulladulla & Districts
Blessing of The Fleet
Parade & Fireworks
Display
2023

Ulladulla Harbour Foreshore & CBD

SUNDAY 9TH APRIL, 2023

MILTON ULLADULLA ROTARY CLUB

TRANSPORT
MANAGEMENT PLAN



TABLE OF CONTENTS

| Contents | |
|---|--------|
| Contents | 1 |
| TMP Event Overview | 1 |
| Planning Contacts | 2 |
| Mission | 4 |
| Situation Analysis | 4 |
| Traffic Arrangements & NSW Workplace Health & Safety (WHS) | 5 |
| Physical Survey of Route | 6 |
| Contingency Plans | g |
| Location of the Event | 11 |
| Parking | 11 |
| Construction, Traffic Generating Developments and Traffic Calming | 11 |
| Traffic Management Requirements Unique to this Event | 11 |
| Access for Local Residents, Businesses & Emergency Services | 11 |
| Event Signage | 11 |
| Staffing | 12 |
| On-road Event Infrastructure | 12 |
| Volunteers and Event Marshals | 12 |
| Other Considerations | 12 |
| Attachments | 12 |
| Contact List | 13 |
| Part 2 Festival Site Plan & Traffic Control Plans | Part 2 |



PART 1 Event Overview

TMP Event Overview

| Event Name: | Ulladulla & Districts Blessing of the Fleet Parade & Fireworks Display |
|------------------|--|
| Event Date: | Sunday 9 th April, 2023 |
| Time: | 0930hrs until 2100hrs |
| Location: | Ulladulla Harbour Foreshore & CBD |
| Event Organiser: | Milton Ulladulla Rotary Club |
| TMP Version: | 1 |
| Revision Date: | 10/03/2023 |
| Document Author: | David Del Tufo |

This Traffic Management Plan is approved by:

| Shoalhaven City Council: | 1 | 1 | |
|--|---|---|--|
| NSW Police (Local Area Command) - Nowra | 1 | I | |

Authority of the TMP

This Traffic Management Plan (TMP) when approved by the relevant authorities becomes the prime document detailing the traffic and transport arrangements under which the Milton Ulladulla Rotary Club will proceed.

Changes to the TMP require the approval of Shoalhaven City Council, NSW Police and NSW Roads & Maritime Services where necessary.

Signatories to this TMP should normally be the agency's senior officer appointed to the operational command team for the event on the day.

In case of emergencies, or for the management of incidents, the NSW Police Force are not subject to the conditions of the TMP but will make every effort to inform the other agencies of the nature of the incident and the Police response.



Planning Contacts

| Rotary Club | | Phillip Brown | า | Position: | Cha | irman | |
|-------------|-----------------------------|---------------|---|-----------|--------------|-------|--|
| Phone: | e: (02) 4454 0842 | | | Mobile: | 0407 272 236 | | |
| Address: | Address: | | | | | | |
| E-mail: | E-mail: pbrown@shoal.net.au | | | | | | |

| NSW Po | lice | Ulladulla Police | Positio | n: | | | |
|----------|--------|------------------|---------|------|--|---------|--|
| Phone: | (02) 4 | 454 8599 | Fax: | Fax: | | Mobile: | |
| Address: | 73 Pri | nces Hwy, Ulladu | lla. | | | | |
| E-mail: | | | | | | | |

| NSW Am | bulance Service | | F | Position: | |
|----------|----------------------|--------|---|-----------|--|
| Phone: | Phone: 000 | | | Mobile: | |
| Address: | 73 Princes Hwy, Ulla | dulla. | | | |
| E-mail: | | | | | |

| Fire & R | Fire & Rescue NSW | | | | Position: | | | | |
|----------|-------------------|--|------|--|-----------|-----|------|--|--|
| Phone: | 000 | | Fax: | | | Mob | ile: | | |
| Address: | | | | | | | | | |
| E-mail: | | | | | | | | | |

| Rural Fi | Rural Fire Service | | | Pos | ition: | | | |
|----------|--------------------|--|------|-----|--------|------|--|--|
| Phone: | 000 | | Fax: | | Mob | ile: | | |
| Address: | | | | | | | | |
| E-mail: | | | | | | | | |

| State Eme | rgency Services | | Position: | | |
|-----------|-----------------|------|-----------|---------|--|
| Phone: | 132 500 | Fax: | 1 | Mobile: | |
| Address: | | | | | |
| E-mail: | | | | | |



| RMS | NSW Ma | aritime | Contact: | | |
|----------|--------|---------|----------|---------|--------------|
| Phone: | | Fax: | | Mobile: | 0431 313 740 |
| Address: | | | | | |
| E-mail: | | | | | |

| Shoalhav | en City Council | Greg Winchester | | Positi | Position: | | ts Liaison Officer |
|---|-----------------------|-----------------|-----|---------|-----------|--|--------------------|
| Phone: | Phone: (02) 4429 3541 | | | Mobile: | | | |
| Address: | PO Box 42, Now | ra NSW 2 | 541 | | | | |
| E-mail: Greg.Winchester@shoalhaven.nsw.gov.au | | | | | | | |

| Dept. Crown Lands | | Linda Ba | la Barr Positio | | sition: | Manager | ast Area | |
|-------------------|-------------|---------------------------------|-----------------|------|----------------|---------|----------|--|
| Phone: | (02) 4428 9 |)108 | | Fax: | (02) 4421 2172 | | Mobile: | |
| Address: | 5 O'Keefe | 5 O'Keefe Ave, Nowra | | | | | | |
| E-mail: | Linda.Barr(| _inda.Barr@crownland.nsw.gov.au | | | | | | |

| Traffic Management Company | | Traffic Professionals | | Contact: | | D | David Del Tufo | |
|-------------------------------|--------------------|--------------------------|---------|----------|--------|------------|----------------|--|
| Phone: | 0488777514 | Fax: | | | Mobile |) : | 0488777514 | |
| Address: | | | | | | | | |
| E-mail: | david@trafficprofe | essionals. | .com.au | | | | | |

| Security Company | | All Areas Protection Services | | | Cont | act: | Scott | |
|------------------|--|-------------------------------|------|--|------|--------|-------|-----------|
| Phone: | | | Fax: | | M | obile: | 0432 | 2 184 884 |
| Address: | | | | | | | | |
| E-mail: | | | | | | | | |

| Fireworks Company | | Xtreme Fireworks | | Contact: | Matt | |
|-------------------|-------------|------------------|----------|----------|---------|--------------|
| Phone: | | | Fax: | | Mobile: | 0411 475 653 |
| Address: | | | | | | |
| E-mail: | matt@xtreme | efirewor | ks.com.a | au | | |

| Carnival Operator | | Jubilee Amusements (East Coast Amusements) | | Contac | t: | | |
|-------------------|----------------|---|------|--------|------|--------------------|-------|
| Phone: | (02) 9651 3183 | | Fax: | | Mobi | e: 0488 923 | 3 779 |
| Address: | | | | | | | , |
| E-mail: | | | | | | | |



Mission

This document – Traffic Management Plan (TMP) aims to provide a plan for vehicular traffic and pedestrian control measures to assist in delivering safe logistical support of the Ulladulla & Districts Blessing of the Fleet Parade & Fireworks Display on Sunday 9th April, 2023. The underlying objective is to minimise safety conflicts between vehicles and pedestrians and disruption to normal vehicular and pedestrian traffic within the Ulladulla Harbour Foreshore & CBD area.

The objectives of this TMP are:

- To provide a high level description of the various traffic management elements needed to make the
 event a success.
- Ensure effective separation between event patrons and participants from vehicular traffic.
- To serve as the key document that is agreed to by all parties and is the final approval to conduct the
 event
- Minimise impact on non-event community and emergency services

Situation Analysis

On Sunday 9th April, 2023 the Ulladulla & Districts Blessing of the Fleet Parade & Fireworks Display will require minimal changes &/or restrictions to vehicle parking arrangements or pedestrian thoroughfare arrangements.

Various sections of the Princes Highway & adjacent roads will be temporarily closed between North Street & Deering Street.

The adjacent road sections include parts of Dolphin Street, North Street, Burrill Street North, Crescent Street, Church Street, Green Street, Boree Street, Wason Street, South Street & Burrill Street South.

There will be on-going reductions in the distance of the closures & sections of the closed road areas as the Blessing of the Fleet Parade of Floats proceeds along the designated route through the Ulladulla CBD area.

The section of the Princes Highway temporarily closed will also be reduced in length once the Parade of Floats is completed & the Parade Floats have made their way out of the CBD area after the Parade Float judging & awards have been presented.

The closed section of the Princes Highway will see through traffic detoured at the intersection of the Princes Highway with North Street (for southbound traffic) & at the intersection of the Princes Highway with Deering Street (for northbound traffic), with the detour route via ST Vincent Street.

Visitors are expected to arrive and depart sporadically throughout the day, prior to and after the Parade of Floats & likewise with the evening Fireworks Display.

The Fireworks Display infrastructure is wholly contained within the area comprising the northern harbour break wall & on pontoons within the harbour.

The Fireworks display will commence at 2000hrs & run until 2030hrs on Sunday 9th April, 2023.



The infrastructure of the Fireworks Display will be removed immediately after the completion of the display.

There will also be a carnival run prior to and after the Parade of Floats.

The Carnival will commence operation at approximately 0900hrs on Sunday 9th April, 2023.

The Carnival will be closed at approximately 1800hrs on Sunday 9th April, 2023.

The carnival is located in the closed section of Green Street between the Princes Highway & Boree Street intersections with Green Street & also including a section of the Ulladulla Civic Centre grounds.

TRAFFIC ARRANGEMENTS & NSW WORKPLACE HEALTH & SAFETY (WHS)

Pedestrian access to the Blessing of the Fleet Parade route areas will be as per usual pathways.

Vehicle movements beyond the Princes Highway (& adjacent road) closure sections will be maintained via sign posted detours utilising ST Vincent Street as the principal route through the Ulladulla Business district.

It is noted that per NSW Workplace Health & Safety (WHS) law the Event Organiser – Milton Ulladulla Rotary Club bears individual risks related to the safety of event patrons and motorists.

The Milton Ulladulla Rotary Club is identified as responsible for event related safety risks which are associated with non-transferable WHS statute-posed obligations and Common Law Duty of Care provisions.

In this context, the Milton Ulladulla Rotary Club should continue to actively consult and take all reasonable measures to practically exercise their duty of care obligations.

These traffic arrangements are detailed in Part 2 – Traffic Arrangements.



Physical Survey of Festival Site

Survey of Route

| Item | Verified 🖂 | Action Taken |
|--------------------------------------|------------|---|
| All one way streets are as described | ⊠ Yes ☐ No | N/A |
| Block access to Church on Sunday | ⊠ Yes ☐ No | Utilise a Traffic Controller position at the Green St/Boree St intersection to ensure access to church carpark is maintained. |
| Block access to local businesses | ⊠ Yes No | Parking areas will allow access to service vehicles for some business properties. Notification to other business properties affected advising of duration of road closure. |
| Block Ambulance access | ⊠ Yes No | Sign posted detours in place. Road closure points are manned. Parking areas will allow access to emergency vehicles. |
| Block Fire & Rescue access | ⊠ Yes⊡ No | Sign posted detours in place. Road closure points are manned. Parking areas will allow access to emergency vehicles. |
| Block heavy vehicle access | ⊠ Yes ☐ No | Sign posted detours in place maintaining heavy vehicle detour. |
| Block hospital access | ⊠ Yes ☐ No | N/A |
| Block local resident access | ⊠ Yes ☐ No | Notification to affected residents advising of duration of road closure. |
| Block Police vehicle access | ⊠ Yes No | Sign posted detours in place. Road closure points are manned. Parking areas will allow access to emergency vehicles. |



| Item | Verified 🖂 | Action Taken |
|---|------------|---|
| Block Public facility (football oval, carpark etc) | ⊠ Yes No | Car parking within Civic Centre grounds, Target Country carpark, Woolworths carpark & Boree St Council carpark will remain operational as per usual. South St Council/ IGA carpark will be manned at entrance/ exit points allowing access/ egress (& advising closure period) during the Parade of Floats. Ulladulla Harbour carpark will be manned at entrance/ exit point allowing access/ egress (& advising closure period) during the Parade of Floats. |
| Block public transport access | ⊠ Yes ☐ No | Sign posted detours in place. |
| Can route use alternatives such as bicycle tracks, paths, parks, bush tracks etc? | ⊠ Yes No | N/A |
| Construction – existing, proposed that may conflict | ⊠ Yes No | Construction site exists at intersection of Burrill St South & Wason St. Site will be closed on Sunday 21st April, 2019. This site infrastructure will have nil impact on parade route or pedestrian access |
| Distance measured is correct | ⊠ Yes No | N/A |
| Lane widths | ⊠ Yes No | N/A |
| Local access | ⊠ Yes No | N/A |
| Numbers of lanes are as described | ⊠ Yes No | N/A |
| Restricted movements – banned turns, heavy/high vehicles | ⊠ Yes No | Proposed detour route enables heavy/ high vehicle thoroughfare. |
| Road signage – existing/temporary | ⊠ Yes No | Advance notification & temporary detour signage. |
| Route impeded by traffic calming devices? | ⊠ Yes No | N/A |



| Item | Verified 🖂 | Action Taken |
|--|------------|--|
| Signalised intersections flashing yellow? Point duty? | ⊠ Yes No | The Traffic Signals at the intersection of the Princes Hwy & Wason St will be disabled & flashing orange during the Parade of Floats & continuing until the re-opening of the Princes Hwy section between Wason St & Deering St. |
| Tidal flows | ⊠ Yes No | To be monitored on the day. |
| Traffic generators – shopping centres, schools, churches, industrial area, hospitals | ⊠ Yes No | All access/ egress roads with restrictions or closures will be manned by traffic controllers to enable use of facilities where possible. |
| Traffic movement contrary to any Notice | ⊠ Yes No | Princes Hwy detour will have heavy vehicle restrictions lifted for the duration of the detour implementation. |
| Traffic signals are as described | ⊠ Yes No | Traffic signals are located at Princes Hwy intersection with Wason St & will be operational as per conditions previously stated. |
| Turning lanes are as described | ⊠ Yes No | N/A |



Contingency Plans

This section of the Traffic Management Plan describes the contingency plans for the event. The contingency plan checklist identifies all possible issues/risks that may interfere with the event and the action to be taken to minimise the disturbance of the event.

Contingency Plan checklist

| Issues/Risks | Applicable | Action Taken |
|---|------------|--|
| Heavy Weather | ⊠ Yes □ No | Rotary Club will decide if the event will begin/continue in the event of severe weather. |
| Lightening, hail, etc. | ⊠ Yes No | Rotary Club will decide if the event will begin/continue in the event of severe weather. |
| Poor Lighting | ⊠ Yes ☐ No | Daytime event. |
| Flood hazard on the route | ⊠ Yes ☐ No | Rotary Club will decide if the event will begin/continue in the event of severe weather. |
| Flood hazard at the parking area | ⊠ Yes ☐ No | All parking areas are sealed. |
| Parking during Wet weather | ⊠ Yes ☐ No | As per regular parking areas. |
| Bush fire hazard | ⊠ Yes No | Follow direction by emergency services |
| Accident on the route | ⊠ Yes No | Follow direction by emergency services. |
| Breakdown | ⊠ Yes ☐ No | Local towing/ breakdown services. |
| Absence of marshals and volunteers | ⊠ Yes ☐ No | Contact Rotary Club |
| Absence of traffic controllers/ advance traffic notification signage. | ⊠ Yes ☐ No | Contact ALBOS Traffic Management |
| Block public transport access | ⊠ Yes ☐ No | Sign posted detours in place. |
| Slow participants | ⊠ Yes ☐ No | Progression of parade floats with support crews & display acts from staging area will be monitored & marshalled to suit. |
| Delayed Event | ⊠ Yes No | Rotary Club to decide |



| Issues/Risks | Applicable | Action Taken |
|--|------------|-----------------------------------|
| Cancellation of Event | ⊠ Yes ☐ No | Rotary Club to decide |
| Security of participants | ⊠ Yes ☐ No | Police & on-site security guards. |
| Security of very important persons (VIP's) | ⊠ Yes ☐ No | Police & on-site security guards. |
| Dual purpose bridge Eg. old Glebe Island Bridge | ☐ Yes ⊠ No | N/A |

A Risk Management approach shall be an integral part of the planning for the Ulladulla & Districts Blessing of the Fleet Parade & Fireworks Display. The risk, identification, assessment and control process is a legal obligation (as per the NSW Workplace Health and Safety Act and Regulation) and should be compliant with AS/NZS ISO 31000:2009. The Milton Ulladulla Rotary Club is responsible for the management of risks arising from the Ulladulla & Districts Blessing of the Fleet Parade & Fireworks Display.

It shall be noted that Traffic Management Plan (TMP) and particularly Traffic Control Plans (TCP) are seen as risk control measures, but alone they cannot substitute and AS/NZS ISO 31000:2009 – compliant and detailed event Risk Assessment.



Traffic and Transport Management

Location of the Event

The Ulladulla & Districts Blessing of the Fleet Parade & Fireworks Display is conducted within the Ulladulla CBD extending from Crescent Street (to the north), South Street (to the south), Boree Street (to the west) & Burrill Street North/ South (to the east).

Parking

Off street parking will be available in all designated parking areas within the Ulladulla Business Precinct as well as on street parking (except for a small section of the Princes Highway) in the surrounding areas as required.

Construction, Traffic Generating Developments and Traffic Calmin

Ulladulla CBD

The Ulladulla CBD contains many businesses which will be operating as usual for a regular Sunday & enjoying significant increases in passing pedestrian traffic.

Traffic Management Requirements Unique to this Event

Refer to Part 2 Traffic Arrangements for details.

Milton Ulladulla Bowling Club & ST Martin's Anglican Church

These community organisations will be operating as usual.

Minimising the Impact on the Non-Event Community & Emergency Services

Access for Local Residents, Businesses & Emergency Services

Local Residents and Businesses:

Ulladulla & Districts Blessing of the Fleet Parade & Fireworks Display arrangements including Princes Highway & adjacent roads closure times will be advertised in the local news media 2 weeks prior to the commencement of the event.

Emergency Vehicle Access:

Emergency Vehicle access will be maintained at all times.

Event Signage

All signage associated with the event is included in the Traffic/ Pedestrian Control Plan (Refer Part 2 Traffic Arrangements for details).



Staffing

The event will be co-ordinated & administered by Milton Ulladulla Rotary Club members.

On-road Event Infrastructure

The Princes Highway will be closed for the section previously detailed with advance temporary road signage & detour instructions for the period previously detailed.

Volunteers, Event Marshals & Formal security Services

All event Marshals will be Rotary Club members.

Site Security will be provided by a licenced & registered security provider with two Security Officers in attendance throughout the event.

Note: this is a non-alcohol event.

Other Considerations

Toilet Facilities & Disabled Access

Access to disabled toilet facilities is available at the Civic Centre building, Boree Street Council Car park, South Street Council Car Park, Deering Street Car Park & Ulladulla Harbour Foreshore (adjacent to Princes Hwy) together with regular toilet facilities.

Additional Portable Toilets

Two portable toilets will be located within the Civic Centre grounds.

First Aid

St John Ambulance first aid staff will be patrolling the event precinct.

Attachments

See Part 2 of this document for Event Layout Plan & Traffic Control Plan.




Contact List


| NAME | ORGANISATION | MOBILE | EMAIL |
|------|--------------|--------|-------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | 1 |




Part 2: Festival Site Plan & Traffic Control Plans


























































































TRAFFIC MANAGEMENT PLAN (TMP)

For

LAZY MOUNTAIN 23 7TH-9TH OF APRIL 2023 BERRY NSW

This TMP is prepared by Vigilant Group on behalf of YOURS AND OWLS' EVENTS
Pty Ltd.

Document Ref # VG6.23.5 V.7: Revision Date:08/03/2023





Contents

| 1. | TMP Scope | 3 |
|-----|---------------------------------|-----|
| 2. | TMP Project Summary and Details | 3 |
| 3. | Event Specific Scope | 3 |
| 5. | TMP Management | 6 |
| 6. | TMP Implementation | 6 |
| 7. | Traffic Guidance Schemes (TGS) | 6 |
| 8. | TGS Attachments | 8 |
| 9. | Risk Management | .10 |
| 10. | Consultation and Contacts List | .11 |
| 11 | TMP Approvals | 11 |







TMP Scope

The scope includes the provision for the safe movement of vehicular and pedestrian traffic, the protection of workers, provision for access to the event site within the designated area of supervision and control, the design, implementation and removal of any necessary temporary roadways and detours including the provision of traffic controllers and all associated temporary signs, road markings and safety requirements.

1. TMP Project Summary and Details

The purpose of this document is to ensure that all conditional requirements relating to the delivery of this TMP are fully documented to support the overall operations of the event. This TMP has been prepared on behalf of **YOURS AND OWLS EVENTS PTY LTD** for their festival accordingly Lazy Mountain 2023. The primary date that this TMP relates to is for the **7**th-**9**th of April 2023. The TMP will focus on **Berry showground**.

This document aims to provide a plan for effective traffic management and co-ordinated management of the above event. The report sets out the procedures by which Local Council and State Government roads may be a partially or full closed to traffic so that the event can proceed accordingly. The document will cover the site as detailed in the contractual agreement throughout all phases of required operation.

Within the document the traffic control measures are unique for the scope of the event and should not be directly applied to any other management plan within the presiding area of the said area of control whether they appear rationally suitable or not.

Primary aim for this TMP is the safe co-ordination of the event through strategic and overall management procedures to ensure the safety of all individuals, groups of individuals including the public and participants, all employees involved in the event both from the organisers and other authorities and stakeholders.

2. Event Specific Scope

This TMP addresses traffic management for the traffic management for the proposed event on behalf of Yours and Owls Events. The plan has been prepared in consultation and agreement with primary stakeholders as listed in section titled Consultation and Contacts list within this TMP. Capacity of 5,000 patrons for the festival in total. All patrons will be travelling by car to the camp site, and patrons will use a mix of transportation methods to access the event site (Tickted festival supplied shuttle buses, trains, walking and private vehicles)

The primary scope of the event is the appropriate measures by which local Councils Roads and RMS roads will be under to Traffic Control Supervision / Control, so the event as proposed can successfully occur. The scope of this TMP has been prepared highlighting the proposed measures that will be undertaken. The fundamental proposal of this TMP is detailed as follows for:





Primary Hours of Control


The designated hours of effect are as follows:

7th of April: 14:00 campsite opens for campers.

8th of April: 12:00-23:00 (event Day)

9th of April: Campground Egress 07:00-15:00

SITE MAP:



023

DESIGNED BY: RAMIE ABOU CHAKRA PWZTMP:0052404132





General Notes

- In accordance with Traffic Management Quality Management processes, it is envisaged and anticipated that there will not be any adverse traffic issues to surrounding streets and the community. All measures will be taken to ensure any foreseeable impacts are mitigated accordingly.
- Estimated number of vehicles are 2,500. Other public transport options available, including Busses, trains, and Private shuttles.
- All traffic controls have been developed as a principle for emergency service vehicles being
 provided primary access to all surrounds of the event accordingly in an event of an
 emergency. Traffic controls and controllers will assist as required to provide uninhibited
 access for emergency vehicles including ushering pedestrians accordingly.
- Arrangements for Heavy Vehicles and Cycle Traffic have not been incorporated within this TMP. The proposed traffic control measures will apply to these modes of transport.
- Pedestrian access will be always maintained to residents within surrounding streets.
- Main intersections where Traffic Controllers cannot be Present VMS boards and / or Signage will be used to direct vehicles.
- All signage required will be installed and removed prior and after the event.
- Contingency plan is expected to be implemented in the event of inclement weather.
- All motorists / Patrons are to adhere to all Current NSW Road Rules.
- Refer to Traffic Guidance Schemes, (TGS) for Site specific details, time of installations, removal of installations.

NOTE: This proposal will be available for the organisers to use for their Public Consultation Process and Procedures

This TMP document supports the following regulatory requirement as applicable in accordance with the defined scope:

RMS Guide to Transport & Management for Special Events v 3.4 RMS Traffic Control at Worksites Manual v 6.1 2022 RMS QA Specification G10 – Traffic Management Ed 5 rev 3 RMS G11 – Road Occupancy Provisions AS1742.3-2019 Manual of Uniform Traffic Control Devices





4. TMP Objectives

The primary objectives of Traffic Control with regards to this Traffic Management Plan are as follows:

- Ensure the safety of all individuals including public, residents and employees to and surrounding the designated area of control
- Minimise any impact or risks relating to the overall flow of motorised vehicle traffic
- Egress and access into the designated area of control and surrounds where applicable to be satisfactorily maintained
- · Minimise primary impacts to surrounding businesses and dwellings
- All formal approvals and licensing as required to be obtained and maintained during the
 duration of the event
- Ensure all environmental procedures are adhered to and maintained in support with other stakeholder and agency requirements
- Any design requirements to be in accordance with RMS Road Design Guidelines and Procedures
- · All relevant statutory requirements as detailed from regulatory agencies to be adhered to.

5. TMP Management

Vigilant Group has warranted and commits to the provision of all resources, systems and associated Traffic Guidance Schemes including traffic management for the event as detailed in the Project Summary and Overview.

All resources in accordance with statutory authorities' requirements will be competent, experienced and qualified to carry out the agreed service as detailed in the binding agreement.

6. TMP Implementation

Traffic Management at the designated areas will be implemented in accordance with RMS Traffic Control at Work Sites Manual and adapted to meet the requirements of the designated areas.

The implementation of the plans will be agreed to with the leading authority/organisers and aligned with the overall planning requirements as detailed in their control measures. This includes the delivery and use of all equipment both dependent and independent of Vigilant Group. The implementation will need to be formally assigned and agreed prior to Work Order establishment.

7. Traffic Guidance Schemes (TGS)

Vigilant Group have developed specifically tailored site-specific TGS that have been prepared in accordance with the specific operational requirements of this event. The TGS and other Movement Plans, both vehicle and pedestrian as required encompass the holistic movements specific and not specific to the event and will incorporate the public also. Any property access affected by the activities will be reviewed and identified in the TGS. The TGS is not a risk management tool in totality but can be used as a support in the overall risk review of the project/event.

At its core any prepared and agreed TGS provides a short-term procedural base for safety management of vehicular and pedestrian flow for the defined project.





Primary Traffic Control

The following traffic control measures are diagrammatically shown and detailed in the Traffic Guidance Schemes (TGS) titled.

- TGS 1: Friday afternoon, around Berry showground. This TGS is for taking out parking and managing the Camping shuttle bus.
- TGS 2A: Campground TGS implementation, reduction of speed and signage to direct campers into the Camping site entrance. (Refer to Speed TGS for detailed implantation of speed reduction)
- TGS 2B: Contingency only if Campground A is full.
- TGS 3: Carpark A, will be activated on Saturday morning. All vehicles parking will be directed
 here via signage and VMS boards. Traffic control to assist with parking vehicles neat. (Refer
 to parking plan)
- TGS 4: Secondary parking area b. this will be used once carpark A is at capacity.
 Implemented once approved by ECC. Signage will be changed to direct all parking vehicles into car park B.
- TGS 5. Contingency egress plan only implemented if Wharf rd becomes congested and we need to use an alternative route to exit the vehicles. This decision will only be made by Event Control.
- TGS 6: Overall ingress plan for Saturday event day. With 2 road closures implemented. 1
 road closer will be Albany st and the 2nd will be Alexandra St. The road can still be used by
 residents, with the assistance of traffic control.
- TGS 7: Overall Egress plan for Saturday event day. Road closures will be implemented around berry showground, with access to all residents. One way system to be implanted around the Venue.
- TGS 8: Detailed plan for the operations on Albany St. one way system in place.
- TGS 9: Detailed Egress plan for Albany st with closure in place and traffic management to allow busses and residents in. One way system in place.
- TGS 10: Detailed ingress plan for the operations on Alexandra St. Road closure in to allow a safe ingress for pedestrians and buses. Residents Access only. Traffic control to manage taxi and Ubers as well.
- TGS 11: Detailed Egress plan for Alexandra St. bus queuing and crowd management.
- TGS 12: Ingress detour plan
- TGS 13: Egress Detour Plan
- TGS 14: overall speed reduction plan.
- TGS 15: Speed reduction plan
- TGS 16: speed reduction plan
- PEDESTRIAN MANAGEMENT PLAN (PMP): a overall of pedestrian movement to and from the event.

VMS / Signage Advisory locations

The following traffic control measures are diagrammatically shown and detailed in the Traffic Guidance Schemes (TGS) titled **Vms plans attached**. Vms to be installed from the 28th of March till the 10th of April 2023. Various locations and messages displayed. Please refer to VMS plans. Additional signage will be implemented for directional purpose.

VMS plan 01,02,03 & 04 attached.





8. TGS Attachments


| Document No | Description | Version | |
|-------------|----------------------------|---------|--|
| TGS 1 | FRIDAY OVERALL PLAN | 1.0 | |
| TGS 2A | CAMPGROUND A | 1.0 | |
| TGS 2B | CAMPGROUND B | 1.0 | |
| TGS 3 | EVENT PARKING A | 1.0 | |
| TGS 4 | EVENT PARKING B | 1.0 | |
| TGS 5 | CONTINGENCY EXIT | 1.0 | |
| TGS 6 | OVERALL INGRESS PLAN | 1.0 | |
| TGS 7 | 6.7 OVERALL EGRESS PLAN | | |
| TGS 8 | ALBANY ST INGRESS PLAN | 1.0 | |
| TGS 9 | ALBANY ST EGRESS PLAN | 1.0 | |
| TGS 10 | ALEXANDRA ST INGRESS PLAN | 1.0 | |
| TGS 11 | 1 ALEXANDRA ST EGRESS PLAN | | |
| TGS 12 | INGRESS DETOUR PLAN | 1.0 | |
| TGS 13 | EGRESS DETOUR PLAN | 1.0 | |
| TGS 14 | SPEED REDUCTION PLAN | 1.0 | |
| TGS 15 | SPEED REDUCTION PLAN | 1.0 | |
| TGS 16 | SPEED REDUCTION PLAN | 1.0 | |
| VMS 1,2,3,4 | VMS LOCATION AND MESSAGING | 1.0 | |
| PMP | Pedestrian management plan | 1.0 | |

Onsite Parking:

Event parking have been organized on TGS 3 & TGS 4 All parking areas have been designed to manage a constant flow of vehicles. TGS 3 has 3 traffic controllers assisting vehicles parking and direction pedestrians to the event site. TGS 5 will be implemented as a contingency. This process will be made by Event Control if Wharf rd is struggling with egress. Attached parking plan:







<u>Camping Shuttle busses:</u>
Campsite shuttle busses have been organized for the event, busses will be picking up patrons from the camp site and using Station st as a bus drop off point. Busses will be running constantly all day to and from the camp site.

A dedicated taxi rank has been established on Alexandria St.

AAA parking and accessibility:
Parking has been established on Albany st, for Accessibility. These spots will be managed by an Authorized traffic controller. AAA and Staff parking available on Station St. Parking will be managed on both Friday Afternoon & all-day Saturday.





PLAN TRAFFIC FLOW AND PARKING:

• Details regarding overflow parking.

Refer to attached internal vehicle flow map, including overflow parking locations

• Numbers, location, and parking requirements for onsite camping.

Patrons will park within their campsite, each camp site has the capacity to fit a Vehicle.

• Wet weather plan.

Damage mitigation tools, such as <u>LD 20</u>, would be used on key grassed thoroughfares to protect the grounds if the surface were soft or at risk of being damaged.

9. Risk Management

Risk management assessment and implementation of this TMP shall be in accordance with the overall risk management of the project and not be kept in isolation. The overall approach with the TMP shall be part of the holistic planning of the event. All risk controls are a legal obligation to be adhered to with relevance to the WHS Act 2012.

Vigilant Group will accommo<mark>date to the management of risks as pre</mark>pared by the client / organisers / principals' representative.

The following have been considered as part of this TMP and as part of Vigilant Group Holistic Risk/Hazard and Verification Assessment:

| Identified Risk | Risk Effect on Event | Controlled Measures |
|--------------------------------|---|---|
| Local Business Access impeded | Possible action against business groups to stifle event | All Businesses to be fully briefed on traffic control measures |
| Emergency Access | Impeding success of event and bad media coverage | All Emergency Services to be briefed and notified of the event by Organisers. Vigilant Group to aid as required |
| Local Residence Access impeded | Risk of backlash from residents | Priority access will be provided under controlled supervision |
| RMS traffic signals | Risk of conflicting traffic control measures | Not affected accordingly, Amber lights may be called in the event of an emergency |
| Adverse weather conditions | Event not proceeding | All control measures will be maintained during all conditions or until organisers inform otherwise. |
| Vehicular Accidents | Event will be delayed | All standard procedures and measures will be undertaken in accordance with current processes. |
| | | |

023






Consultation and Contacts List

| Name | Organisation | Contact | Approving Authority (Yes / No) |
|-------------------|-----------------------------|------------|--------------------------------------|
| Nathaniel Holmes | Architects of Entertainment | 0422169363 | Υ |
| Georgie Hanrahan | Architects of Entertainment | 0434520616 | У |
| RMS | Roads and Maritime Services | 131 700 | Υ |
| Ramie Abou chakra | Vigilant Group | 0431811489 | Υ |
| | | | Υ |





























11/06/2023

THIS PLAN IS NOT TO SCALE



Cs Required

6 X TC

2 X UTES


9AM

23:59PM

Speed Reduction:


Nearest Cross St

STATION RD




MAP LOCATION























SIGNALIZED INTERSECTIONS)
2: EVENT
3: ONE (1) LANE OF TRAFFIC ACCESS
MAINTAINED PAST WORK AREA AT ALL TIMES
4: A RISK ASSESSMENT MUST BE COMPLETED

SECTION 3.3, 4.3, 5.3.
8: WORKSITE SHOULD BE CONTINUALLY
MONITORED AS PER PART 6 SECTION 7.3.
9: TOS REMOVAL MUST BE FOLLOWED AS
PER PART 6 SECTION 7.3.
10: TGS MUST BE IMPLEMENTED BY A

10: IGS MUST BE IMPLEMENTED BY A
CERTIFIED S. COMPETENT PERSON AS PER
PART 8 SECTION 6.6.
11: TGS MUST ONLY BE IMPLEMENTED DURING
APPROVED HOURS OF ROAD AUTHORITY.
12: ANY MODIFICATIONS TO THIS TGS MUST
BE NOTED.

| RECOMMENDED TAPER LENGTH | | | | | | |
|---|--|---------------------------|----------------|--|--|--|
| APPROXIMATE SPEED OF TRAFFIC KM/H | TRAFFIC CONTROL AT BEGINNING OF TAPER | LATERAL SHIFT TAPER | MERGE TAPER | | | |
| 45 OR LESS | 15 | 0 | 15 | | | |
| 46 - 55 | 15 | 15 | 30 | | | |
| 56 - 65 | 30 | 30 | 60 | | | |
| 66 - 75 | N/A | 70 | 115 | | | |
| 76 - 85 | N/A | 80 | 130 | | | |
| 86 - 95 | N/A | 90 | 145 | | | |
| 96 - 105 | N/A | 100 | 160 | | | |
| > 105 | N/A | 110 | 180 | | | |
| D | IMENSON ' | "D" | | | | |

| SPEED OF TRAFFIC | | | |
|------------------|-----------|------|--|
| KM/H | AS.1742.3 | TC@W | |
| 45 OR LESS | 15m | 15m | |
| 46 - 55 | 15m | 50m | |
| 56 - 65 | 45m | 60m | |
| GREATER THAN | EQUAL TO | | |
| 65 KM/H | | | |

TOLERANCES POSITIONING OF SIGNS

MINIMUM 10% LESS THAN
THE DISTANCE OR LENGTHS GIVEN MAXIMUM 25% MORE THAN THE DISTANCE OR LENGTHS GIVEN SPACING OF DELINEATING DEVICES MAXIMUM 10% MORE THAN THE SPACING GIVEN NO MINIMUM

LANE WIDTHS


THE MIN LANE WIDTH TO BE PROVIDED THROUGH OR PAST THE WORKSITE SHALL BE 3.0m (3.5m DESIRABLE 2.8m min)

QUEUE MANAGEMENT PLAN

AT ALL TIMES DURING THE COURSE OF THE WORK TRAFFIC QUEUES SHALL BE MONITORED TO ENSURE THAT TRAFFIC DOES NOT EXCEED BEYOND THE LIMITS OF ADVANCED WARNING SIGNS

TCAWS V 6.1 HIS DRAWING IS TO BE READ IN

CONJUNCTION WITH AS1742.3 TCAWS TFNSW.VERSON 6.1






| LINGOIN U. I | | | | | | | | |
|--------------------|------------------|---------|----------------------|--------------|------------------|-----------------|----------------|-------------------|
| Client: | LAZY MOUNTAIN | INGRESS | ROL Required: | NO | Date Prepared: | 03/01/2023 | Designed By: | Ramie Abou Chakra |
| Road Name: | BERRY SHOWGROUND | | ROL Number: | N/A | Date Approved: | 03/01/2023 | Accreditation: | PWZTMP |
| Suburb: | BERRY | | Road Classification: | COUNCIL ROAD | TC@WS Reference: | BASED ON TCP 41 | Ticket Number: | 0052404132 |
| TCs Required | 9 X TC 1 X TS | | Speed Reduction: | TBC | SAMS Number: | | Expiry Date: | 11/06/2023 |
| Vehicles Required: | 2 X UTES | | Nearest Cross St: | STATION RD | TCP Ref Number: | TGS 9 EGRESS | Signature: | APPROVED |



THIS PLAN IS NOT TO SCALE






Nearest Cross St:

STATION RD


TCP Ref Number:

TGS 10





















1: CATEGORY 2 (HIGHER-VOLUME ROADS & SIGNALIZED INTERSECTIONS)

SIGNALIZED INTERSECTIONS)
2: LANE CLOSUIRE
3: ONE (1) LANE OF TRAFFIC ACCESS
MAINTAINED PAST WORK AREA AT ALL TIMES
4: A RISK ASSESSMENT MUST BE COMPLETED
PRIOR TO IMPLEMENTING TES AS PER
PART 6 SECTION 6
5: TRAFFIC CONTROL DEVICES TO BE
INSTALLED AND USED AS PER PART 6 SECTION
64, 65, 66, 67, 68

6.4, 6.5, 6.6, 6.7, 6.8
6: PEDESTRIAN ACCESS TO BE MAINTAINED AS
PER PART 3 SECTION 3.10.1, 4.10.1
7: WORK AREA IS TO BE CLEARLY DEFINED
WITH A PHYSICAL BARRIER AS PER PART 3
SECTION 3.3, 4.3, 5.3.

SECTION 3.3, 4.3, 5.3.

S: WORKSITE SHOULD BE CONTINUALLY
MONITORED AS PER PART 6 SECTION 7.3.

9: TGS REMOVAL MUST BE FOLLOWED AS
PER PART 6 SECTION 7.3.

10: TGS MUST BE IMPLEMENTED BY A
CERTIFIED & COMPETENT PERSON AS PER
PART 8 SECTION 6.8

PART 8 SECTION 6.6.

11: TGS MUST ONLY BE IMPLEMENTED DURING

APPROVED HOURS OF ROAD AUTHORITY.

12: ANY MODIFICATIONS TO THIS TGS MUST BE NOTED.

| RECOMMENDED TAPER LENGTH | | | | | | | | |
|---|--|---------------------------|----------------|--|--|--|--|--|
| APPROXIMATE SPEED OF TRAFFIC KM/H | TRAFFIC CONTROL AT BEGINNING OF TAPER | LATERAL SHIFT TAPER | MERGE TAPER | | | | | |
| 45 OR LESS | 15 | 0 | 15 | | | | | |
| 46 - 55 | 15 | 15 | 30 | | | | | |
| 56 - 65 | 30 | 30 | 60 | | | | | |
| 66 - 75 | N/A | 70 | 115 | | | | | |
| 76 - 85 | N/A | 80 | 130 | | | | | |
| 86 - 95 | N/A | 90 | 145 | | | | | |
| 96 - 105 | N/A | 100 | 160 | | | | | |
| > 105 | N/A | 110 | 180 | | | | | |

| | | ON "D" | |
|-------------|-----|-----------|-------|
| SPEED OF TR | | | |
| KM/H | | AS.1742.3 | TC@WS |
| 45 OR LES | S | 15m | 15m |
| 46 - 55 | | 15m | 50m |
| 56 - 65 | | 45m | 60m |
| GREATER TH | IAN | | AL TO |
| 65 KM/H | | POSTE | SPEED |

TOLERANCES

MINIMUM 10% LESS THAN THE DISTANCE OR LENGTHS GIVEN MAXIMUM 25% MORE THAN THE DISTANCE OR LENGTHS GIVEN SPACING OF DELINEATING DEVICES MAXIMUM 10% MORE THAN THE SPACING GIVEN NO MINIMUM

LANE WIDTHS


THE MIN LANE WIDTH TO BE PROVIDED THROUGH OR PAST THE WORKSITE SHALL BE 3.0m (3.5m DESIRABLE 2.8m min)

QUEUE MANAGEMENT PLAN

AT ALL TIMES DURING THE COURSE OF THE WORK TRAFFIC QUEUES SHALL BE MONITORED TO ENSURE THAT TRAFFIC DOES NOT EXCEED BEYOND THE LIMITS OF ADVANCED WARNING SIGNS

TCAWS V 6.1

HIS DRAWING IS TO BE READ IN CONJUNCTION WITH AS1742.3 & TCAWS TFNSW.VERSON 6.1







1: CATEGORY 2 (HIGHER-VOLUME ROADS & SIGNALIZED INTERSECTIONS)
2: LANE CLOSURE
3: ONE (1) LANE OF TRAFFIC ACCESS MAINTAINED PAST WORK AREA AT ALL TIMES 4: A RISK ASSESSMENT MUST BE COMPLETED PRIOR TO IMPLEMENTING TGS AS PER PART 6 SECTION 5

FART 0 SECTION 5 5: TRAFFIC CONTROL DEVICES TO BE INSTALLED AND USED AS PER PART 6 SECTION 6.4, 6.5, 6.6, 6.7, 6.8

6: PEDESTRIAN ACCESS TO BE MAINTAINED AS PER PART 3 SECTION 3.10.1, 4.10.1 7: WORK AREA IS TO BE CLEARLY DEFINED WITH A PHYSICAL BARRIER AS PER PART 3 SECTION 3.3, 4.3, 5.3.

SECTION 3.3, 4.3, 5.3.

8: WORKSITE SHOULD BE CONTINUALLY MONITORED AS PER PART 6 SECTION 7.3.

9: TGS REMOVAL MUST BE FOLLOWED AS

9: TGS REMOVAL MUST BE FOLLOWED AS PER PART 6 SECTION 7.3. 10: TGS MUST BE IMPLEMENTED BY A CERTIFIED & COMPETENT PERSON AS PER PART 8 SECTION 6.6. 11: TGS MUST ONLY BE IMPLEMENTED DURING APPROVED HOURS OF ROAD AUTHORITY. 12: ANY MODIFICATIONS TO THIS TGS MUST BE NOTED.

| RECOMME | NDED TAP | ER LEN | GTH |
|-------------|------------|---------|-------|
| APPROXIMATE | | LATERAL | MERGE |
| CDEED OF | CONTROL AT | CHIET | TADED |

| SPEED OF TRAFFIC KM/H | CONTROL AT BEGINNING OF TAPER | SHIFT TAPER | TAPER |
|--------------------------|-------------------------------------|----------------|-------|
| 45 OR LESS | 15 | 0 | 15 |
| 46 - 55 | 15 | 15 | 30 |
| 56 - 65 | 30 | 30 | 60 |
| 66 - 75 | N/A | 70 | 115 |
| 76 - 85 | N/A | 80 | 130 |
| 86 - 95 | N/A | 90 | 145 |
| 96 - 105 | N/A | 100 | 160 |
| > 105 | N/A | 110 | 180 |

| ı | DIMENSON "D" | | | | | |
|---|------------------|---------------|-------|--|--|--|
| | SPEED OF TRAFFIC | DIMINESON D=M | | | | |
| | KM/H | AS.1742.3 | TC@WS | | | |
| | 45 OR LESS | 15m | 15m | | | |
| | 46 - 55 | 15m | 50m | | | |
| | 56 - 65 | 45m | 60m | | | |
| | GREATER THAN | | AL TO | | | |
| | 65 KM/H | POSTE | SPEEL | | | |

TOLERANCES

MINIMUM 10% LESS THAN THE DISTANCE OR LENGTHS GIVEN MAXIMUM 25% MORE THAN THE DISTANCE OR LENGTHS GIVEN SPACING OF DELINEATING DEVICES MAXIMUM 10% MORE THAN THE SPACING GIVEN NO MINIMUM

LANE WIDTHS


THE MIN LANE WIDTH TO BE PROVIDED THROUGH OR PAST THE WORKSITE SHALL BE 3.0m (3.5m DESIRABLE 2.8m min)

QUEUE MANAGEMENT PLAN


AT ALL TIMES DURING THE COURSE OF THE WORK TRAFFIC QUEUES SHALL BE MONITORED TO ENSURE THAT TRAFFIC DOES NOT EXCEED BEYOND THE LIMITS OF ADVANCED WARNING SIGNS

TCAWS V 6.1


THIS DRAWING IS TO BE READ IN CONJUNCTION WITH AS1742.3 & TCAWS TFNSW.VERSON 6.1


















| Client: | LAZY MOUNTAIN | ROL Required: | YES | | 03/01/2023 | Designed By: | Ramie Abou Chakra |
|--------------------|---------------|----------------------|-------------|------------------|-----------------|----------------|-------------------|
| Road Name: | PRINCES HWY | ROL Number: | N/A | Date Approved: | 03/01/2023 | Accreditation: | PWZTMP |
| Suburb: | BERRY | Road Classification: | STATE ROAD | TC@WS Reference: | BASED ON TCP 41 | Ticket Number: | 0052404132 |
| TCs Required | | Speed Reduction: | TBC | SAMS Number: | | Expiry Date: | 11/06/2023 |
| Vehicles Required: | | Nearest Cross St: | PRINCES HWY | TCP Ref Number: | VMS 2 | Signature: | APPROVED |





